

BID ITEM LIST

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0001	070030	LEAD COMPLIANCE PLAN	LS	LUMP SUM
0002	080060	LEVEL 2 CRITICAL PATH METHOD SCHEDULE	LS	LUMP SUM
0003	090100	TIME-RELATED OVERHEAD (WDAY)	WDAY	186
0004	090205	DISPUTE RESOLUTION BOARD ON-SITE MEETING	EA	8
0005	090210	HOURLY OFF-SITE DISPUTE-RESOLUTION-BOARD-RELATED TASKS	HR	40
0006	100100	DEVELOP WATER SUPPLY	LS	LUMP SUM
0007	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM
0008	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM
0009	120103	STATIONARY IMPACT ATTENUATOR VEHICLE	DAY	186
0010	120165	CHANNELIZER (SURFACE MOUNTED)	EA	90
0011	010413	PORTABLE RADAR SPEED FEEDBACK SIGN SYSTEMS (LS)	LS	LUMP SUM
0012	120320	TEMPORARY BARRIER SYSTEM	LF	3,360
0013	124000	TEMPORARY PEDESTRIAN ACCESS ROUTE	LS	LUMP SUM
0014	128652	PORTABLE CHANGEABLE MESSAGE SIGN (LS)	LS	LUMP SUM
0015	014105	ALTERNATIVE TEMPORARY CRASH CUSHION TL-3	EA	6
0016	129161	AUTOMATED FLAGGER ASSISTANCE DEVICE DAY	EA	186
0017	130100	JOB SITE MANAGEMENT	LS	LUMP SUM
0018	130201	WATER POLLUTION CONTROL PROGRAM	LS	LUMP SUM
0019	130500	TEMPORARY EROSION CONTROL BLANKET	SQYD	6,250
0020	130510	TEMPORARY MULCH	SQYD	6,250

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0021	130570	TEMPORARY COVER	SQYD	6,250
0022	130620	TEMPORARY DRAINAGE INLET PROTECTION	EA	66
0023	130640	TEMPORARY FIBER ROLL	LF	4,760
0024	130650	TEMPORARY GRAVEL BAG BERM	LF	130
0025	130670	TEMPORARY REINFORCED SILT FENCE	LF	60
0026	130680	TEMPORARY SILT FENCE	LF	1,600
0027	130710	TEMPORARY CONSTRUCTION ENTRANCE	EA	32
0028	130720	TEMPORARY CONSTRUCTION ROADWAY	SQYD	3,460
0029	130730	STREET SWEEPING	LS	LUMP SUM
0030	130900	TEMPORARY CONCRETE WASHOUT	LS	LUMP SUM
0031	131103	WATER QUALITY SAMPLING AND ANALYSIS DAY	EA	20
0032	131104	WATER QUALITY MONITORING REPORT	EA	12
0033	131105	WATER QUALITY ANNUAL REPORT	EA	2
0034	131201	TEMPORARY CREEK DIVERSION SYSTEMS	LS	LUMP SUM
0035	146002	CONTRACTOR-SUPPLIED BIOLOGIST (LS)	LS	LUMP SUM
0036	146003	NATURAL RESOURCE PROTECTION PLAN	LS	LUMP SUM
0037	016104	AQUATIC SPECIES PROTECTION AND RELOCATION	LS	LUMP SUM
0038	146007	INVASIVE SPECIES CONTROL	LS	LUMP SUM
0039	153213	REMOVE CONCRETE (STRUCTURE)	CY	21
0040	160110	TEMPORARY HIGH-VISIBILITY FENCE	LF	780

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0041	170103	CLEARING AND GRUBBING (LS)	LS	LUMP SUM
0042	190123	ROADWAY EXCAVATION (TOPSOIL)	CY	22
0043	198010	IMPORTED BORROW (CY)	CY	270
0044	204020	PLANT (GROUP P)	EA	50
0045	204099	PLANT ESTABLISHMENT WORK	LS	LUMP SUM
0046	205035	WOOD MULCH	CY	99
0047	210010	MOVE-IN/MOVE-OUT (EROSION CONTROL)	EA	3
0048	037634	HYDRAULIC BIOTIC GROWTH MEDIUM	SQFT	56,600
0049	210255	FIBER REINFORCED MATRIX (SQFT)	SQFT	56,600
0050	210270	ROLLED EROSION CONTROL PRODUCT (NETTING)	SQFT	2,800
0051	210350	FIBER ROLLS	LF	4,520
0052	210610	COMPOST (CY)	CY	6
0053	210630	INCORPORATE MATERIALS	SQFT	550
0054	260203	CLASS 2 AGGREGATE BASE (CY)	CY	20
0055	390132	HOT MIX ASPHALT (TYPE A)	TON	38
0056	394073	PLACE HOT MIX ASPHALT DIKE (TYPE A)	LF	78
0057	394075	PLACE HOT MIX ASPHALT DIKE (TYPE D)	LF	590
0058	394076	PLACE HOT MIX ASPHALT DIKE (TYPE E)	LF	30
0059	394090	PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA)	SQYD	9
0060	398100	REMOVE ASPHALT CONCRETE DIKE	LF	250

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0061	510092	(F) - STRUCTURAL CONCRETE, HEADWALL	CY	61.4
0062	510094	STRUCTURAL CONCRETE, DRAINAGE INLET	CY	72
0063	039504	STRUCTURAL CONCRETE (JUNCTION STRUCTURE)	CY	15
0064	610300	CONCRETE BACKFILL (PIPE TRENCH)	CY	79
0065	015420	CONCRETE COLLAR	EA	4
0066	641101	12" PLASTIC PIPE	LF	11
0067	650014	18" REINFORCED CONCRETE PIPE	LF	140
0068	650018	24" REINFORCED CONCRETE PIPE	LF	1,840
0069	650022	30" REINFORCED CONCRETE PIPE	LF	5
0070	650026	36" REINFORCED CONCRETE PIPE	LF	82
0071	650030	42" REINFORCED CONCRETE PIPE	LF	10
0072	650038	54" REINFORCED CONCRETE PIPE	LF	10
0073	665012	12" CORRUGATED STEEL PIPE (.079" THICK)	LF	19
0074	017721	14" X 24" ELLIPTICAL CORRUGATED STEEL PIPE	LF	10
0075	665018	18" CORRUGATED STEEL PIPE (.109" THICK)	LF	37
0076	017722	24" X 48" ELLIPTICAL CORRUGATED STEEL PIPE	LF	290
0077	665024	24" CORRUGATED STEEL PIPE (.109" THICK)	LF	1,920
0078	665033	30" CORRUGATED STEEL PIPE (.138" THICK)	LF	500
0079	665038	36" CORRUGATED STEEL PIPE (.138" THICK)	LF	320
0080	665713	12" SLOTTED CORRUGATED STEEL PIPE (.109" THICK)	LF	20

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0081	680607	8" NON-PERFORATED STEEL PIPE UNDERDRAIN (.079" THICK)	LF	20
0082	690112	12" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	LF	260
0083	690117	18" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	LF	5
0084	690124	24" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	LF	1,220
0085	690132	30" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	LF	110
0086	690137	36" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	LF	58
0087	690147	48" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	LF	91
0088	692005	12" ENTRANCE TAPER	EA	3
0089	692009	24" ENTRANCE TAPER	EA	2
0090	692305	12" ANCHOR ASSEMBLY	EA	9
0091	692309	24" ANCHOR ASSEMBLY	EA	61
0092	692311	30" ANCHOR ASSEMBLY	EA	6
0093	692313	36" ANCHOR ASSEMBLY	EA	5
0094	039795	CABLE ANCHORAGE SYSTEM	EA	10
0095	017720	48" ANCHOR ASSEMBLY	EA	4
0096	700617	DRAINAGE INLET MARKER	EA	12
0097	700641	36" CORRUGATED STEEL PIPE INLET (.168" THICK)	LF	29
0098	702616	24" CORRUGATED STEEL PIPE ENERGY DISSIPATOR (.064" THICK)	EA	3
0099	016831	48" WELDED STEEL PIPE (.750" THICK) (TRENCHLESS)	LF	400
0100	705011	18" STEEL FLARED END SECTION	EA	3

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0101	705015	24" STEEL FLARED END SECTION	EA	7
0102	705019	30" STEEL FLARED END SECTION	EA	1
0103	705206	24" CONCRETE FLARED END SECTION	EA	2
0104	015173	36" TRENCHLESS WELDED STEEL PIPE (0.625" THICK)	LF	690
0105	707117	36" PRECAST CONCRETE PIPE INLET	LF	29
0106	709522	INLET DEPRESSION	EA	4
0107	710102	ABANDON CULVERT (LF)	LF	2,230
0108	710126	REMOVE OVERSIDE DRAIN	EA	3
0109	710132	REMOVE CULVERT (LF)	LF	4,300
0110	037172	REMOVE SLOTTED CORRUGATED STEEL PIPE	LF	20
0111	710138	REMOVE DOWNDRAIN (EA)	EA	19
0112	710150	REMOVE INLET	EA	53
0113	710152	REMOVE HEADWALL	EA	16
0114	014818	REMOVE PCC APRON	EA	9
0115	710165	REMOVE CONCRETE FLARED END SECTION (EA)	EA	1
0116	710167	REMOVE FLARED END SECTION (EA)	EA	5
0117	710368	CULVERT SLURRY-CEMENT BACKFILL	CY	380
0118	721431	CONCRETE (CONCRETE APRON)	CY	63
0119	013729	GRAVEL FILTER	CY	77
0120	723040	ROCK SLOPE PROTECTION (3/8 T, CLASS VI, METHOD B) (CY)	CY	29

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0121	723050	ROCK SLOPE PROTECTION (1/4 T, CLASS V, METHOD B) (CY)	CY	15
0122	723060	ROCK SLOPE PROTECTION (300 LB, CLASS IV, METHOD B) (CY)	CY	55
0123	723070	ROCK SLOPE PROTECTION (150 LB, CLASS III, METHOD B) (CY)	CY	12
0124	723080	ROCK SLOPE PROTECTION (60 LB, CLASS II, METHOD B) (CY)	CY	16
0125	723095	ROCK SLOPE PROTECTION (20 LB, CLASS I, METHOD B) (CY)	CY	17
0126	750001	(F) - MISCELLANEOUS IRON AND STEEL	LB	12,386
0127	800101	TEMPORARY FENCE (TYPE BW)	LF	160
0128	820112	MARKER (CULVERT)	EA	75
0129	820220	REMOVE MARKER	EA	75
0130	820510	RESET ROADSIDE SIGN (ONE POST)	EA	9
0131	839521	(F) - CABLE RAILING	LF	188
0132	870009	MAINTAINING EXISTING TRAFFIC MANAGEMENT SYSTEM ELEMENTS DURING CONSTRUCTION	LS	LUMP SUM
0133	872133	MODIFYING SIGNAL AND LIGHTING SYSTEMS	LS	LUMP SUM
0134	872137	MODIFYING CHANGEABLE MESSAGE SIGN SYSTEMS	LS	LUMP SUM
0135	999990	MOBILIZATION	LS	LUMP SUM