



List of Bid Items

Note: *This list is not updated when addenda are issued. For informational purposes only.*

Contract Number **05-1K1204**

Date Adv.: 09/19/2022

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
1	070030	LEAD COMPLIANCE PLAN	LS	LUMP SUM
2	080060	LEVEL 2 CRITICAL PATH METHOD SCHEDULE	LS	LUMP SUM
3	090100	TIME-RELATED OVERHEAD (WDAY)	WDAY	250
4	090200	DISPUTE RESOLUTION ADVISOR ON-SITE MEETING	EA	6
5	090207	HOURLY OFF-SITE DISPUTE-RESOLUTION-ADVISOR-RELATED TASKS	HR	10
6	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM
7	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM
8	120149	TEMPORARY PAVEMENT MARKING (PAINT)	SQFT	48
9	120159	TEMPORARY TRAFFIC STRIPE (PAINT)	LF	2,260
10	120165	CHANNELIZER (SURFACE MOUNTED)	EA	20
11	120320	TEMPORARY BARRIER SYSTEM	LF	1,080
12	128652	PORTABLE CHANGEABLE MESSAGE SIGN (LS)	LS	LUMP SUM
13	014249	ALTERNATIVE TEMPORARY CRASH CUSHION	EA	4
14	130100	JOB SITE MANAGEMENT	LS	LUMP SUM
15	130200	PREPARE WATER POLLUTION CONTROL PROGRAM	LS	LUMP SUM
16	130620	TEMPORARY DRAINAGE INLET PROTECTION	EA	4
17	130660	TEMPORARY LARGE SEDIMENT BARRIER	LF	800
18	130900	TEMPORARY CONCRETE WASHOUT	LS	LUMP SUM
19	141103	REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE (HAZARDOUS WASTE)	LF	3,530
20	141120	TREATED WOOD WASTE	LB	430
21	170103	CLEARING AND GRUBBING (LS)	LS	LUMP SUM
22	190101	ROADWAY EXCAVATION	CY	5,660
23	192020	(F) - STRUCTURE EXCAVATION (TYPE D)	CY	285

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
24	048376	(F) - STRUCTURE EXCAVATION (SOLDIER PILE WALL TYPE D)	CY	363
25	193003	(F) - STRUCTURE BACKFILL (BRIDGE)	CY	87
26	193029	(F) - STRUCTURE BACKFILL (SOLDIER PILE WALL)	CY	142
27	193116	(F) - CONCRETE BACKFILL (SOLDIER PILE WALL)	CY	265
28	193119	(F) - LEAN CONCRETE BACKFILL	CY	115
29	198010	IMPORTED BORROW (CY)	CY	1,820
30	014250	CONTOUR LOG	EA	12
31	202006	SOIL AMENDMENT	CY	1.7
32	202038	PACKET FERTILIZER	EA	96
33	204009	PLANT (GROUP I)	EA	36
34	204010	PLANT (GROUP O)	EA	60
35	204013	PLANT (GROUP M)	EA	40
36	014251	PLANT (GROUP N)	EA	290
37	204099	PLANT ESTABLISHMENT WORK	LS	LUMP SUM
38	205035	WOOD MULCH	CY	1.4
39	205051	FOLIAGE PROTECTOR	EA	28
40	014252	TREE SHELTER	EA	120
41	206300	TEMPORARY IRRIGATION SYSTEM	LS	LUMP SUM
42	210010	MOVE-IN/MOVE-OUT (EROSION CONTROL)	EA	2
43	210270	ROLLED EROSION CONTROL PRODUCT (NETTING)	SQFT	190
44	014253	COMPOST BERM	LF	660
45	210430	HYDROSEED	SQFT	11,600
46	210610	COMPOST (CY)	CY	35
47	260203	CLASS 2 AGGREGATE BASE (CY)	CY	56
48	390132	HOT MIX ASPHALT (TYPE A)	TON	430
49	397005	TACK COAT	TON	0.6
50	398200	COLD PLANE ASPHALT CONCRETE PAVEMENT	SQYD	250
51	048377	STEEL SOLDIER PILE (HP 18 X 204)	LF	2,098
52	490403	30" DRILLED HOLE	LF	2,276
53	490601	16" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	48
54	490603	24" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	112

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
55	490605	36" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	126
56	490683	24" CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET)	LF	144
57	048378	36" CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET)	LF	252
58	510053	(F) - STRUCTURAL CONCRETE, BRIDGE	CY	106
59	510054	(F) - STRUCTURAL CONCRETE, BRIDGE (POLYMER FIBER)	CY	404
60	510072	(F) - STRUCTURAL CONCRETE, BARRIER SLAB	CY	55
61	510094	(F) - STRUCTURAL CONCRETE, DRAINAGE INLET	CY	3.1
62	048379	(F) - STRUCTURAL CONCRETE, CAP BEAM	CY	75
63	519088	JOINT SEAL (MR 1")	LF	51
64	519102	JOINT SEAL (TYPE AL)	LF	418
65	520102	(F) - BAR REINFORCING STEEL (BRIDGE)	LB	170,200
66	048380	(F) - BAR REINFORCING STEEL (CAP BEAM)	LB	14,900
67	575004	(F) - TIMBER LAGGING	MFBM	31
68	590120	CLEAN AND PAINT STEEL SOLDIER PILING	LS	LUMP SUM
69	650018	24" REINFORCED CONCRETE PIPE	LF	49
70	710102	ABANDON CULVERT (LF)	LF	120
71	710132	REMOVE CULVERT (LF)	LF	54
72	710150	REMOVE INLET	EA	2
73	723050	ROCK SLOPE PROTECTION (1/4 T, CLASS V, METHOD B) (CY)	CY	68
74	723080	ROCK SLOPE PROTECTION (60 LB, CLASS II, METHOD B) (CY)	CY	5
75	723180	CONCRETED-ROCK SLOPE PROTECTION (60 LB, CLASS II, METHOD B) (CY)	CY	85
76	729011	ROCK SLOPE PROTECTION FABRIC (CLASS 8)	SQYD	340
77	750001	(F) - MISCELLANEOUS IRON AND STEEL	LB	480
78	750501	(F) - MISCELLANEOUS METAL (BRIDGE)	LB	842
79	780446	STAIN GALVANIZED SURFACES (LS)	LS	LUMP SUM
80	780450	ROCK STAIN	SQFT	810
81	800103	TEMPORARY FENCE (TYPE CL-6)	LF	610
82	810120	REMOVE PAVEMENT MARKER	EA	160

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
83	810230	PAVEMENT MARKER (RETROREFLECTIVE)	EA	160
84	820250	REMOVE ROADSIDE SIGN	EA	1
85	820750	FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-UNFRAMED)	SQFT	9
86	820840	ROADSIDE SIGN - ONE POST	EA	1
87	014254	ALTERNATIVE CRASH CUSHION (TL-2)	EA	2
88	014255	(F) - CONCRETE BARRIER (TYPE 842B) (MOD)	LF	23
89	839746	(F) - CONCRETE BARRIER (TYPE 842)	LF	158
90	839749	(F) - CONCRETE BARRIER (TYPE 842 MODIFIED)	LF	390
91	839752	REMOVE GUARDRAIL	LF	220
92	839775	REMOVE CONCRETE BARRIER (TYPE K)	LF	460
93	839782	REMOVE CRASH CUSHION	EA	3
94	846007	6" THERMOPLASTIC TRAFFIC STRIPE (ENHANCED WET NIGHT VISIBILITY)	LF	6,660
95	846030	REMOVE THERMOPLASTIC TRAFFIC STRIPE	LF	2,260
96	872002	TEMPORARY SIGNAL SYSTEMS	LS	LUMP SUM
97	999990	MOBILIZATION	LS	LUMP SUM